


## CHAPTER-15

### PAINTING AND DISTEMPERING

S. No.	SCH. P.W.D	Description of Work	UNIT	OVER ALL RATE
1	2	3	4	5
1	641	Painting or Vanishing on iron works in small areas or new wood work with one coat of ready mixed priming paint & one coat of approved superior ready mixed paint of clear sythetic varnish including supply of all materials, labour and T & P etc. required for proper completion of work. Paint to be used should confirm to the I.S.I. No. 103 1950.	Sqm.	59.40
2	642	Same as in item 641 above but for every coat after 1st coat Details of coat for 650 sft. Area.	Sqm.	28.20
3	643	As in item no-642 above but every coat on previously painted old wood or steel work.	Sqm.	38.30
4	644	Painting roofs or orther iron work in large area with one coat of ready mixed paint priming one coat of approved paint (British ANTISOL) including supply of all materials, labour & T & P etc. required for proper completion of the work. Paint to be used should confirm I.S.I. No. 103-1950. Coat for area of 650 sft. Priming coat.	Sqm.	47.30
5	645	As in item no-644 above but every coat after the first coat.	Sqm.	22.15
6	646	As in item no-645 above but for every coat on previously painted old surface.	Sqm.	32.20
7	649	One priming coat & one coat oil distemper on new work including supply of all materials, labour and T & P etc. required for proper completion of the work.	Sqm.	45.30
8	650	As in item no-649 above but for every coat after the first coat.	Sqm.	21.15
9	651	As in item no-650 above but for every coat on previously old distempered surface	Sqm.	25.20
10	652	One coat hot coaltar on new surface including supply of all materials, labour and T & P etc. required for proper completion of work.	Sqm.	16.10
11	653	One coat hot coaltar but every coat after 1st coat previously painted surface including supply of all materials, labour and T & P etc. required for proper completion of the work.	Sqm.	11.10
12	654	One coat solignum or other approved preservative on new wood. Including supply of all materials, labour and T & P etc required for proper completion of the work.	Sqm.	29.20
13	655	As in item no.-654 above but for every coat after first coat on previously treated surface.	Sqm.	22.15
14	656	Oiling wood work with double boiled linseed oil including supply of all materials, labour and T & P etc required for proper completion of the work. Details for an area of 700 sfts.	Sqm.	13.10
15	657	Removing paint or varnish with paint remover or caustic soda, Including supply of all materials, labour and T & P etc required for proper completion of the work.	Sqm.	45.30
16	658	Wax polishing new wood work with approved ready made wax polish or approved French polish after rubbing down with sand paper Including supply of all materials, labour and T & P etc required for proper completion of the work.	Sqm.	52.40
17	659	As in item no 658 above but replishing wood work already wax or French polished with approved realy made wax polish or approved French polish Including supply of all materials, labour and T & P etc required for proper completion of the work	Sqm.	26.20
18	660	Finishing walls with water proof cement paint of approved make and quality on new work with two coats to give an even shade. Including supply of all material, labour and T & P etc required for proper completion of the work	Sqm.	48.30
19	661	Same as in item no 660 but for each coat of water proof cement paint after the first two coats to give an even shade.	Sqm.	17.10
20	662	Finishing walls with one coat of water proof cement paint of approved quality on previously old treated surface with this paint to give an even shade Including supply of all material, labour and T & P etc required for proper completion of the work.	Sqm.	28.20

  
**( GYAN PRAKASH PANDEY )**  
**SUPERINTENDING ENGINEER**  
**AZAMGARH CIRCLE, P.W.D.,**  
**AZAMGARH**