


Chapter 17

DEMOLITION AND DISMANTLING

S.No.	Sch. PWD	Description of item	Unit	Over All Rate
1	2	3	4	5
1	691	Dismantling sundried brick work including stacking of dismantled materials as directed by Engineer-inCharge within a distance of 60 meters (200feet).	Cu.M	61.40
2	692	Dismantling brick work or stone work in lime or cement mortar and including stacking of materials as directed by the Engineer-in-charge within a distance of 60 meters(200 feet)	Cu.M	322.00
3	693	As in item(692) above but in mud mortar.	Cu.M	161.00
4	694	Dismantling reinforced cement concrete or reinforced brick work including stacking of dismantled materials as directed by the Engineer-in-charge within a distance of 60M (200feet)	Cu.M	705.00
5	695	Dismantling jack arched or wooden beam and bargas roofs, including beams and roof concrete an including stacking of dismantled materials as directed by the Engineer-in-charge within a distance of 60 metres(200 feet).	Sq.M	181.00
6	696	As in item(695) above but only roof concrete.	Cu.M	250.00
7	697	Dismantling cement concrete or brick or granolithic floors including stacking of dismantled materials as directed by the Engineer-in-charge with in distance of 60 Metres(200 feet).	Sq.M	37.20
8	698	As in item(697) above but floor to be stone flagged or tiled floor.	Sq.M	50.30
9	699	Dismantling single tiled roof,any kind, including purlin and battens and including stacking of dismantled materials as directed by the Engineer-in-charge with in distance of 60 metres (200 feet)	Sq.M	54.30
10	700	As in item(699) above but double tiled floor.	Sq.M	92.50
11	701	Dismantling corrugated iron roofs walls or partition including purlins battens and vertical support and including stacking of materials as directed by the Engineer-in-charge with a distance of 60 metres. (200 feet).	Sq.M	31.20
12	702	Dismantling of gurder,trusses and other steel work including stacking of dismantled materials as directed by the Engineer-in-charge with a distance of 60 metres .(200 feet).	Qtl.	1055.00
13	703	Dismantling doors or windows Chaukhats with hold fasts & including stacking of dismaneteled materials as directed by the Engineer-in-charge with a distance of 60 metres (200feet).	Sq.M	49.20
14	704	Dismantling doors or windows leaves including stacking of materials as directed by the Engineer-in-charge with a distance of 60 metres (200feet).	Sq.M	24.10
15	705	Dismantling doors or windows including chaukhats but excluding hold fasts and including stacking of materials as directed by the Engineer-in-charge with a distance of 60 metres(200 feet).	Sq.M	46.25
16	706	Dismantling existing plaster including disposal of refuse as directed by the Engineer-in-charge with a distance of 60 metres (200feet).	Sq.M	26.10
17	707	Racking out joints of brick work in cement or lime mortar to depth of 1cm.(3/8") including disposal of refuse as directed by the Engineer-in-charge with a distance of 60 metres (200feet).	Sq.M	19.10
18	708	Scraping old white or colour wash including disposal of refuse as directed by the Engineer-in-charge with a distance of 60 metres(200feet).	Sq.M	8.05


(GYAN PRAKASH PANDEY)
SUPERINTENDING ENGINEER
AZAMGARH CIRCLE, P.W.D.,
AZAMGARH