


Chapter 25 DRAINAGE

S.No.	Sch. PWD	Item No. NBO	Description of item	Unit	Labour Rate
1		24.1	Laying stoneware pipe(to level or slopes) and jointing with stiff mixture of cement mortal in ratio of 1:1(cement & fine sand) including testing of pipes and joints complete.		
			a- 100mm dia	R.M.	29.00
			b- 150mm dia.	R.M.	40.00
2		24.7	Laying cement concrete 1:5:10 in haunching S.W. pipes including concrete for bedding,necessary from work & curing complete.	R.M.	35.00
3		24.18	Laying jointing pointing with a stiff mixture of cement mortar in ratio 1:1(cement and fine sand) salt glazed S.W. or white glazed half round channels.	R.M.	21.00
4		24.19	Fixing S.W. gully trap grade"A" complete with C.I.grating,brick masonry chamber &water tight C.I.cover frame of 300 mmx300mm size(inside) square mouth traps or "P" or "S" type traps.	Each	99.00
5		24.27	Constrcting man hole with R.C.C. top slab in 1:2:4 mix foundation concrete 1:4:8 mix inside plaster 15mm thick with cement mortar 1:3(Cement and fine sand) with a floating coat of neat cement and making channels in cement concrete 1:2:4 mix finished smooth including curing and testing.		
			(a) Inside size 800x800mm and 500mm deep including C.I. cover frame.	Each	549.00
			(b) Inside size 1200mmx900mm and 1.0 metre deep including C.I. cover and frame.	Each	1054.00
6		24.28	Extra over item No. 24.27 for every additional depth of 0.10 metre or part there of main hole		
			(a) Size 800x800mm	R.M.	29.00
			(b) Size 1200x900mm	R.M.	31.00
7		24.36	Making connection of drain or sewer line with existing man hole including breaking into and making good walls, floors with cement concrete,1:2:4 cement plastered on both side with cement mortar 1:3 finished with a floating coat of neat cement and making necessary channels with cement concrete 1:2:4 for the drain etc, complete.	Each	59.00


 (GYAN PRAKASH PANDEY)
 SUPERINTENDING ENGINEER
 AZAMGARH CIRCLE, P.W.D.,
 AZAMGARH