

## CHAPTER -6(Brick Work)

Sl.No.	Description Of Work	Unit	Rate			
			Full item Rate			Labour Rate
			Jalaun	Jhansi	Lalitpur	
1	2	3	4	5	6	7
301	First class brick work in kankar lime and surkhi in proportion of 1:3 in foundation and plinth including supply of all materials, labours and T & P etc. required for proper completion of the	cum	5574.80	6051.30	6478.80	697.20
302	first class brick work in one white lime and two surkhi mortar in foundation and plinth including supply of all materials, labour and T & P etc. required for Proper completion of the work.	cum	5759.80	6464.60	7096.70	697.20
302.a	First class brick work in one white lime and three surkhi mortar in foundation and plinth including supply of all materials labour and T & P etc required for proper completion of the work.	cum	5639.50	6365.00	7015.70	697.20
303	First class brick work in 1:6 cement and fine sand of 1.25 FM. mortar in foundation and plinth including supply of all materials, labour and T & P etc. required for proper completion of the work.	cum	5320.10	5726.80	6293.60	697.20
304	As in item (303) above but in 1:5 cement and find sand of 1.25 F.M. mortar.	cum	5407.60	5814.30	6381.20	697.20
305	As in item No. 303 above but in 1 : 4 cement and fine sand of 1.25 F.M. mortar.	cum	5495.20	5901.80	6468.70	697.20
306	As in.item No. 303 above but in 1:3 cement and fine sand of 1.25 F. M. mortar	cum	5757.70	6164.40	6731.20	697.20
307	As in.item No. 303 above but in 1:3 cement and coarse sand mortar	cum	5765.40	6172.00	6738.90	697.20
308	first class brick work in mud mortar in foundation and plinth including supply of all materials, labour and T & P etc required for proper completion of the work	cum	4437.80	4906.60	5327.10	697.20
309	As in item (301 to (304) above but in super-structure. including necessary cutting and moulding of bricks as required and also - including honey comb brick work, thickness of wall not to be less than 1.5 brick thick. Add extra labour to above item no. 301 to 304	cum	238.30	238.30	238.30	238.30
310	As in item (309) above but for wall of one brick thick. Add for extra labour.	cum	224.80	224.80	224.80	224.80
310 (a)	As in item (309) above but for wall of half brick (4 1/2") thick. Add for Extra labour over Item No. 310.	cum	337.20	337.20	337.20	337.20
310 (b)	As in Item (309) above but wall upto 3" thick Add for extra labour over item No 310(a)	cum	493.00	493.00	493.00	493.00

