


**CHAPTER-12**  
**CEILING AND LINING**

Sl. No.	DESCRIPTION OF ITEMS	UNIT	Jalaun	Jhansi	Lalitpur	Labour Rate
1	2	3	4	5	6	7
16.7	Providing and fixing 6 mm thick fiber hard board sheet lining with but jointing and nails (Frame work and cover fillets to be measured and paid for separately)	Sqm.	204.00	204.00	204.00	51.00
16.9	(a) Providing and fixing veneered particle board 12 mm thick lining measured and paid for separately)	Sqm.	576.00	576.00	576.00	144.00
	(b) 20 mm thick particle board.	Sqm.	648.00	648.00	648.00	162.00
16.10	Providing and fixing decorative type veneered particles board 12 mm thick lining with but jointing and nails (Frame work be paid Separately).	Sqm.	576.00	576.00	576.00	144.00
16.13	Providing and fixing 12 mm thick plywood lining with but jointing and nails (Frame work and cover fillets to be paid and measured Separately).	Sqm	420.00	420.00	420.00	105.00
16.35	Providing and fixing 12 mm thick plaster of Paris (Gypsum anhydrous) ceiling tiles upto height of 5 meters above floor level over wooden frame and rendered smooth with plaster of Paris (Frame work to be measured and paid for separately).	Sqm	576.00	576.00	576.00	144.00
6(a)	<b>Perforated ceiling tiles</b> :- Providing and fixing in position teak wood perforated practice board ceiling tiles bonded with B.W.P type Phenol formaldehyde synthetic Resin tiles in size 60x60x12 mm over kail wood timber frame of 50 mm x 38 mm section and suspended from the roof with the help of flat iron Hangers of size 3.0 mm x 45 mm. on under side leaving an expansion gap of 6 mm and with provision for providing necessary lighting fixtures including three cost of felt oil paint of approved quality and shade and a coat of pink prime/copal varnish of the side facing the roof as per direction given by Engineer-in charge.	Sqm	1440.00	1440.00	1440.00	360.00
(b)	Same as above but with decorative ceiling tiles.	Sqm	1470.00	1470.00	1470.00	367.50
7(a)	<b>Wooden Partition</b> : Providing and fixing in position 38 mm thick single skin partition with fibre or particle board frame of 900X400 mm section of 75 mm X 38 mm and fixing (Paneled type) 19 mm thick teak wood particle board bounded with phenol formaldehyde synthetic resin both face commercial confirming to I.S.I specification No.3097-1980 as per drawing complete with painting/French polish/Wax polish or as per direction given by Engineer-in- charge.	Sqm	1560.00	1560.00	1560.00	390.00
(b)	Same as in item no.7(a) above but with 19 mm thick teak wood particle board laminated on both faces.	Sqm.	2580.00	2580.00	2580.00	645.00

*S. E. J. S.*

*[Signature]*

SI. No.	DESCRIPTION OF ITEMS	UNIT	Jalaun	Jhansi	Lalitpur	Labour Rate
1	2	3	4	5	6	7
8(a)	Providing and fixing in position double skin wooden partition with fibre or particle board frame of 900 X 1200 rectangular of section 50 X 38 mm covered with 12 mm thick teak wood particle board commercial quality on both face duly painted two coats of high gloss synthetic enamel paint over one priming paint complete.	Sqm.	2220.00	2220.00	2220.00	555.00
(b)	Same as in item No. 8(a) above but covering with 12 mm thick teak wood particle board laminated on both faces.	Sqm.	2280.00	2280.00	2280.00	570.00
9(a)	Wall Panelling providing and fixing in position wall panels of plain phenol formaldehyde synthetic resin tiles over kail wood frame and provision for providing switch board fixtures etc. as per drawing complete with polishing and fining with French/Wax polish as per direction given Engineer-in-charge.	Sqm.	1440.00	1440.00	1440.00	360.00
(b)	Same as in item No.9(a) above but with one side laminated instead of plain board.	Sqm.	1980.00	1980.00	1980.00	495.00

  
 (Er. Shripal Singh)  
 Superintending Engineer  
 Jhansi Circle, P.W.D., Jhansi  
 22.10.2024