

| |
|-------------------|
| Chapter 24 |
| DRAINAGE |

| S.No. | Sch. PWD | Item No. NBO | Description of item | Unit | Labour Rate |
|-------|----------|--------------|--|------|-------------|
| 1 | | 24.1 | Laying stoneware pipe(to level or slopes) and jointing with stiff mixture of cement mortal in ratio of 1:1(cement & fine sand) including testing of pipes and joints complete. | | |
| | | | a- 100mm dia | R.M. | 29.00 |
| | | | b- 150mm dia. | R.M. | 40.00 |
| 2 | | 24.7 | Laying cement concrete 1:5:10 in haunching S.W. pipes including concrete for bedding,necessary from work & curing complete. | R.M. | 35.00 |
| 3 | | 24.18 | Laying jointing pointing with a stiff mixture of cement mortar in ratio 1:1(cement and fine sand) salt glazed S.W. or white glazed half round channels. | R.M. | 21.00 |
| 4 | | 24.19 | Fixing S.W. gully trap grade"A" complete with C.I.grating,brick masonry chamber &water tight C.I.cover frame of 300 mmx300mm size(inside) square mouth traps or "P" or "S" type traps. | Each | 99.00 |
| 5 | | 24.27 | Constrcting man hole with R.C.C. top slab in 1:2:4 mix foundation concrete 1:4:8 mix inside plaster 15mm thick with cement mortar 1:3(Cement and fine sand) with a floating coat of neat cement and making channels in cement concrete 1:2:4 mix finished smooth including curing and testing. | | |
| | | | (a) Inside size 800x800mm and 500mm deep including C.I. cover frame. | Each | 549.00 |
| | | | (b) Inside size 1200mmx900mm and 1.0 metre deep including C.I. cover and frame. | Each | 1054.00 |
| 6 | | 24.28 | Extra over item No. 24.27 for every additional depth of 0.10 metre or part there of main hole | | |
| | | | (a) Size 800x800mm | R.M. | 29.00 |
| | | | (b) Size 1200x900mm | R.M. | 31.00 |
| 7 | | 24.36 | Making connection of drain or sewer line with existing man hole including breaking into and making good walls, floors with cement concrete,1:2:4 cement plastered on both side with cement mortar 1:3 finished with a floating coat of neat cement and making necessary channels with cement concrete 1:2:4 for the drain etc, complete. | Each | 59.00 |

(Gyan Prakash Pandey)
Superintending Engineer
Azamgarh Circle, P.W.D.,
Azamgarh