

CHAPTER-4**EARTH WORK**

(For Building Estimate Only)

SI No.	SCH P.W.D.	ITEM No.	Description of items of work	P.W.D. Specification	Unit No	Labour Rate
1	2	3	4	5	6	7
1	251		Excavation in foundation in ordinary soil (loamclay or sand) including lift up to 1.5m and lead up to 30m. and including filling watering and ramming of excavated earth into the space between the building and the sides of foundation trenches or into the plinth and removal and disposal of surplus earth as directed by the Engineer in charge up to a distance of 30m. from the foundation trenches including all T&P phowarah and basket etc. complete.	4.1.1	Cum	99.00
2	MORD 11.1		Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.			176.00
3	252		As in item NO. 251 above but excavation in soil mixed with moorum/shingle/black cotton/ kankar requiring the use of special T&P such as pickaxe, subbals etc.	4.1.3	Cum.	118.00
4	253		Earth work in cutting or in embankment in ordinary soil excavation to be the form of regular pits not exceeding ½ meter (20") in depth and earth work in embankment to be in 20cm (8") layers, including ramming and dressing the surface to required levels and slopes and also including 1.5m (5") lift and 30m (100') lead. The earth form cutting to be used in making embankment or to be deposited as spoil banks within 30m (100') distance as directed by the E/l.		Cum	80.00

Note : Royalty if levied shall be paid extra as per rules.

(Gyan Prakash Pandey)
Superintending Engineer
Azamgarh Circle, P.W.D.,
Azamgarh