

**CHAPTER-6**  
**BRICK WORK**

S.No.	SCH. P.W.D	ITEM NO NBO	Description of Work	P.W.D SPEC. NO.	UNIT	LABOUR RATE	OVER ALL RATE
1	2	3	4	5	6	7	8
1	303	(a)	Class-150 brick work in 1 : 6 cement and coarse sand mortar in foundation and plinth including supply of all materials, labour and T & P etc. required for proper completion of the work.	6.1.1	Cu.M		4650.00
2	305		As in item 303 above but in 1 : 4 cement and coarse sand	6.1.3	Cu.M		5300.00
3	307		As in item 303 above but in 1 : 3 cement and coarse sand mortar.	6.1.5	Cu.M		5600.00
4	309		As in item (303a to 307) above but in the super-structure including necessary cutting and moulding of bricks as required and also including honey comb brick, work thickness of wall not to be less than 1½ brick thick. Add for extra labour to above items.	6.1.6	Cu.M		230.00
5	310		As in item 309 above but for wall of one brick thick. Add for extra labour.		Cu.M		200.00
6	310(a)		As in item 310 above but for wall of half brick thick. Add for extra labour.		Cu.M		100.00
7	310(b)		As in item 310 (a) above but for wall of 3" brick thick. Add for extra labour.		Cu.M		140.00

NOTE :- An increase of 5% per floor will be allowed in labour rate Component only or 1% per floor for over all rate.