

CHAPTER-17
DEMOLITION AND DISMANTLING

S.No.	SCH. P.W.D	ITEM NO PWD	Description of Work	P.W.D SPEC. NO.	UNIT	LABOUR RATE	OVER ALL RATE
1	2	3	4	5	6	7	8
1		692	Dismantling brick work or stone work in lime or cement mortar and including stacking of materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Cu.M	-	320.00
2		693	As in item (692) above but in mud mortar.		Cu.M	-	155.00
3		694	Dismantling reinforcement cement concrete or reinforcement brick work including stacking of materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Cu.M	-	715.00
4		695	Dismantling Jack arched or wooden beam and barja roofs including beam and roof concrete and including stracking dismantled materials as directed.		Sqm.	-	180.00
5		696	As in item (695) above but only roof concrete.		Cu.M	-	250.00
6		697	Dismantling cement concrete or brick work or granolithic floors including stacking of dismantled materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Sqm.	-	38.00
7		698	As in item (697) above but floor to be stone flagged or tiled floor		Sqm.	-	50.00
8		701	Dismantling corrugated iron roofs walls or partition including purlins battens and vertical support and including stacking of dismantled materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Sqm.	-	32.00
9		702	Dismantling of grids, trusses and other steel work including stacking of dismantled materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Qtl	-	1100.00
10		703	Dismantling doors or windows including stacking of dismantled materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Sqm.	-	50.00

S.No.	SCH. P.W.D	ITEM NO PWD	Description of Work	P.W.D SPEC. NO.	UNIT	LABOUR RATE	OVER ALL RATE
1	2	3	4	5	6	7	8
11		704	Dismantling doors or windows leaves including stacking of dismantled materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Sqm.	-	25.00
12		705	Dismantling doors or windows leaves excluding chaukhat including stacking of dismantled materials as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Sqm.	-	48.00
13		706	Dismantling existing plaster including disposal of refuse as directed by Engineer-in-charge with in a distance of 60 mt. (200 feet)		Sqm.	-	27.00
14		707	Racking out joints of brick work in cement or lime mortar to depth of 1 cm (3/8") including disposal of refuse material as directed by Engineer-in-charge with a distance of 60 met.(200 feet)		Sqm.	-	19.00
15		708	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distance of 60 met.(200 feet)		Sqm.	-	8.00