

Chapter 19

MICELLANEOUS

S.No.	Sch. PWD	Item No. NBO	Description of item	P.W.D. Spec. No.	Unit	Labour Rate	Over All Rate
1	730		Supply and fixing of 10cm internal Dia Ac Down pipes complete with rose-heads bends M.S. Clamps 2.5cmx3mm fixed walls by 15cm. Long 6mm Dia nail sand including repair of plaster pointing etc. If damaged during fixing of the pipes including cost of all material labours,Tools and Plants etc. required for proper completion of work.	21.5	R.M.		122.00
2			seamless one peace moulded tanks and placing the				
			(a) For 200 litres.		Lit		10.00
			(b) For 300 litres.		Lit		10.00
			(c) For 500 litres.		Lit		10.00
3			Supply and hoisting Ferrocement tanks and placing				
			(a) For 200 litres.		Each	129.00	132.00
			(b) For 300 litres.		Each	167.00	170.00
			(c) For 500 litres.		Each	198.00	203.00
4a			Supply and fixing of anodised Aluminium door having 2mm thick Aluminium section excluding coating & an average coating of 20 micron fully glazed made of Aluminium door tube size 83.5x44.65mm as Vertical member and 1140x44.45mm size tube in bottom & horizontal members Door chaukhat should be of Aluminium tublar vertical with two openable shutters.The rate will include cost of material fixture 4mm glass handles,locks,screw necessary beeding & excluding cost of floor spring if required for proper completiion of work as per direction of Engineer I/C		Sq.M		4432.00
4b			Same as in item 4(a) but with 5.00mm thick plain glass complete.		Sq.M		4606.00

(Gyan Prakash Pandey)
Superintending Engineer
Azamgarh Circle, P.W.D.,
Azamgarh